BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of Work: Drilling of Borewell, Providing and Installing Pump, Motor and other accessories and Development of Parks and Providing Children Play and Gym Equipments at NTI Layout, Gurudharshan Layout in Ward No. 09 (Vidyarnayapura).

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
1	2	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its quality & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Each BW	3768.00	Rupees Three Thousand Seven Hundred Sixty Eight Only
2	100.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars and cap etc.,) ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 0 to 50 m	Rmtr	347.00	Rupees Three Hundred Forty Seven Only
3	100.00	50 to 100 m	Rmtr	442.00	Rupees Four Hundred Forty Two Only
4	100.00	100 to 150 m	Rmtr	456.00	Rupees Four Hundred Fifty Six Only
5	100.00	150 to 200 m	Rmtr	536.00	Rupees Five Hundred Thirty Six Only
6	100.00	200 to 250 m	Rmtr	634.00	Rupees Six Hundred Thirty Four Only
7	100.00	250 to 300 m	Rmtr	700.00	Rupees Seven Hundred Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
8	10[illegible]0	300 to 350 m	Rmtr	825.00	Rupees Eight Hundred Twenty Five Only
9	160.00	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by baseic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985, one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and durties) Prices include Collar-medium duty	Rmtr	1380.00	Rupees One Thousand Three Hundred Eighty Only
10	36.00	Providing 250mm dia PVC Pipe 6kg/cm etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	1100.00	Rupees One Thousand One Hundred Only
11	2	Providing and fixing Borewell Cap & Clamp Set etc., complete and as per the directions of the Engineer-in-charge of the work	Set	1800.00	Rupees One Thousand Eight Hundred Only
12	2	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps etc., complete and as per the directions of the Engineer-in-charge of the work	No	63498.00	Rupees Sixty Three Thousand Four Hundred Ninety Eight Only
13	640.00	GI Pipe 50 mm'B' class etc., complete and as per the directions of the Engineer-in-charge of the work	m	415.00	Rupees Four Hundred Fifteen Only
14	108	Heavy Duty Collar 50 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	180.00	Rupees One Hundred Eighty Only
15	2	Providing non-return valve 50 mm etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	1800.00	Rupees One Thousand Eight Hundred Only
16	10	Providing Gate Valve 50 mm etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	1800.00	Rupees One Thousand Eight Hundred Only
17	2	Supplying and Fixing Out Door Panel up to 15 HP etc., complete and as per the directions of the Engineer-in-charge of the work	No.	15500.00	Rupees Fifteen Thousand Five Hundred Only
18	1320.00	Submersible Cable 1x3x6.0 Sq.mm etc., complete and as per the directions of the Engineer-in-charge of the work	M	144.00	Rupees One Hundred Forty Four Only
19	108	Labour charges for erection as new /repaired submercible pumpset allong with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset shoud be handed over to department including transportation (Each lenth =6.00) etc., complete and as per the directions of the Engineer-in-charge of the work	Per Length	88.00	Rupees Eighty Eight Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
20	2	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., complete and as per the directions of the Engineer-in-charge of the work	Each	292.00	Rupees Two Hundred Ninety Two Only
21	70.00	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A **4 core 16 Sqmm** etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	150.00	Rupees One Hundred Fifty Only
22	70.00	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	11.88	Rupees Eleven And Paise Eighty Eight Only
23	60.00	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	76.00	Rupees Seventy Six Only
24	8.00	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	335.00	Rupees Three Hundred Thirty Five Only
25	2	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	270.00	Rupees Two Hundred Seventy Only
26	2	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	No	2999.70	Rupees Two Thousand Nine Hundred Ninety Nine And Paise Seventy Only
27	12	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	174.00	Rupees One Hundred Seventy Four Only
28	2	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. **5-32Amps Group A TPN** etc., complete and as per the directions of the Engineer-in-charge of the work	No	1715.00	Rupees One Thousand Seven Hundred Fifteen Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
29	46800.00	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete and as per the directions of the Engineer-in-charge of the work	Sq.Cm	0.35	Rupees And Paise Thirty Five Only
30	72.00	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strata by Manual Means etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	262.00	Rupees Two Hundred Sixty Two Only
31	200.00	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	207.00	Rupees Two Hundred Seven Only
32	24.00	Filling the foundations KSRRB 2100-6. Filling the foundations trenches using approved sand as per drawing and technical specifications in 250mm layers, wherever necessary watering and ramming, including cost of all materials, labour complete as per specifications.	cum	3221.34	Rupees Three Thousand Two Hundred Twenty One And Paise Thirty Four Only
33	48.00	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including watering, consolidation in layers of 15 cm thick including disposing of the sunplus earth with a lead of 200 mtrs etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	103.00	Rupees One Hundred Three Only
34	64.35	Earthwork in surface excavation in **ordinary soil** for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.	Cum	352.14	Rupees Three Hundred Fifty Two And Paise Fourteen Only
35	7.56	Providing and laying in position **plain cement concrete of mix 1:4:8** with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation**, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5408.12	Rupees Five Thousand Four Hundred Eight And Paise Twelve Only
36	22.68	Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6, stone** hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	4871.76	Rupees Four Thousand Eight Hundred Seventy One And Paise Seventy Six Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
37	17.01	Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	5811.98	Rupees Five Thousand Eight Hundred Eleven And Paise Ninety Eight Only
38	37.80	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. – do – cement mortar 1:3	sqm	100.70	Rupees One Hundred And Paise Seventy Only
39	81.00	Filling the foundations trenches using approved sand as per drawing and technical specifications in 250mm layers, wherever necessary watering and ramming, including cost of all materials, labour complete as per specifications.	cum	3221.34	Rupees Three Thousand Two Hundred Twenty One And Paise Thirty Four Only
40	21.78	Providing and laying in position **plain cement concrete of mix 1:2:4** with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation, plinth and cills**, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5811.98	Rupees Five Thousand Eight Hundred Eleven And Paise Ninety Eight Only
41	180.00	Providing and laying flooring using **prepolished, water cut/gang saw 19mm thick granite** laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials and labours etc., complete as per specifications. - **using silver grey granite / Multy Red / Ruby Red / Black / HassanGreen Granite of width not less than 1200 mm**	Sqm	2903.34	Rupees Two Thousand Nine Hundred Three And Paise Thirty Four Only
42	850.00	Providing and laying **heavy duty cobble stones 60mm thick interlock pavers**, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	1116.18	Rupees One Thousand One Hundred Sixteen And Paise Eighteen Only
43	1200	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc complete as per specifications and directions of engineer in charge of the work	No	440.64	Rupees Four Hundred Forty And Paise Sixty Four Only
44	486.00	Providing and applying **ready mix priming coat over** concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	39.96	Rupees Thirty Nine And Paise Ninety Six Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
45	486.00	Providing and applying **spray painting in two coats (excluding priming coat)** over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	91.80	Rupees Ninety One And Paise Eighty Only
46	2	Supply and fixing of pull down challenger: Metal All tubular steel of 2.50 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as neccessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixing. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a 5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must the worksply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2015x615x1360mm weight :93 kg safety Area 5015x3015 mm capacity_2 persons .):	Nos	239400.00	Rupees Two Lakh(s) Thirty Nine Thousand Four Hundred Only
47	2.00	Supply and fixing of Seated Chest Press Metal All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a 5% NaCl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clear the workbe in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certificates. Size (Lx	Each	229425.00	Rupees Two Lakh(s) Twenty Nine Thousand Four Hundred Twenty Five Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
48	2	Supply and fixing of Self Weighted Rower All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly dip the workbe in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certificates.	Each	164587.50	Rupees One Lakh(s) Sixty Four Thousand Five Hundred Eighty Seven And Paise Fifty Only
49	2	Supply and fixing of Elliptical cross Trainer metalAll tubular steel of 2.5 mm thickness are galavnized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must c the worksply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2015x615x1360mm weight :93 kg safety Area 5015x3015 mm capacity_2 persons	Nos	139650.00	Rupees One Lakh(s) Thirty Nine Thousand Six Hundred Fifty Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
50	2	Supply and fixing of Rider metal All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the the worksply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2015x615x1360mm weight :93 kg safety Area 5015x3015 mm c	Nos	89775.00	Rupees Eighty Nine Thousand Seven Hundred Seventy Five Only
51	2	Supply and fixing of Bicycle Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply t the workbe in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certificate	Each	124687.50	Rupees One Lakh(s) Twenty Four Thousand Six Hundred Eighty Seven And Paise Fifty Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
52	2	Supply and fixing of Twist Stepper All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply t the workbe in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certif	Each	179550.00	Rupees One Lakh(s) Seventy Nine Thousand Five Hundred Fifty Only
53	2	Supply and fixing of Big shoulder wheel All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disp the worksply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2015x615x1360mm weight :93 kg safety Area 5015x3015 mm capacity	Each	119700.00	Rupees One Lakh(s) Nineteen Thousand Seven Hundred Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
54	2	Supply and fixing HD Health Walker All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply th the worksply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2015x615x1360mm weight :93 kg safety Area 5015x3015 mm cap	Each	139650.00	Rupees One Lakh(s) Thirty Nine Thousand Six Hundred Fifty Only
55	2	Supply and fixing HD Squat Pushing Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly di the workbe in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certificates. Size	Each	214462.50	Rupees Two Lakh(s) Fourteen Thousand Four Hundred Sixty Two And Paise Fifty Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
56	2	Supply and fixing Mini Ski. Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly diply the the workbe in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certific	Each	159600.00	Rupees One Lakh(s) Fifty Nine Thousand Six Hundred Only
57	2	Supply and fixing of HD Double Health Walker Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixing. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must c the worksply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2015x615x1360mm weight :93 kg safety Area 5015x3015 mm capacity_2 persons .	Each	239400.00	Rupees Two Lakh(s) Thirty Nine Thousand Four Hundred Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
58	2	Supply and fixing of HD Waist Twister Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped joints are robotic welded all welded joints are scalloped as necessary and welded to an approved MIG process All welds are dressed off removing all sharp edges and burrs Zonc primer paint is applied at all the welding points prior to finishing all metal parts are powder coated using AKZO Nobel Grate wall powder to the thickness of 80-120 microns all metal parts are tested in our salt spray machine that uses a 5% NACI solution in accordance to ISO7227 to speed up corrosion for 3000 hrs Rubber: High quality grip rubber is used for the handles Bearings: Maintenance free ball berings Scope of delivery 1 Completely pre assembled equipment modules Maintenance: Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certifica the worksply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2015x615x1360mm weight :93 kg safety Area 5015x3015 mm capacity_2 persons .): 1460 x 1310 x 1150 mm weight : 39.1 kg safety Area 4360 x 4510 mm capacity_3 persons .	Each	130000.00	Rupees One Lakh(s) Thirty Thousand Only
59	5	Supplying of Granite benches as per approved drawing including cost of steel, materials, labour, transportation etc complete as per specification (Approved Rate)	Nos	10500.00	Rupees Ten Thousand Five Hundred Only

"DTS APPROVED"

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))